Tremco CPG UK Limited
Cavendish House, Unit 1, Enterpris
NUDURA ICF - STOCK SUPI
DISTRIBUTOR BILL OF MA

PROJECT DETAILS
Estimate Number
Date
Valid Until
Site Name
Client (end user)
Distributor

Scope

DISTRIBUTOR DETAILS (please
Distributor Company Name
Contact Name
Contact Email
Contact Phone
Your Reference

INSTRUCTIONS: Yellow-highlighted

ES26-088
02/11/2026
02/12/2026
Badgers Hollow, Alderley Edge
Mr Imran Kara
Ethos Property Developments (Mark Whalley)

Basement extension (below lower ground): 450 core + 200 core walls, 7 courses. Stock forms, uncut, +5% waste.

Ethos Property Developments
Mark Whalley

cells are editable. Enter your sale rates on the "Bill of Materials" sheet rate card; line totals and the "Pricing Sun

nmary" sheet update automatically.

DISTRIBUTOR RATE CARD

Enter YOUR sale rate (ex VAT) for each item in the yellow cells - they flow through the whole Bill of Materials

SKU	Description	Category
NUS-IXPAN-00	450 core - XR35 Panel (unassembled)	ICF FORMS
NUS-I0B96-00	450 core - Unassembled Brick Ledge 96in (bundle 2 BL + 2 std panels)	ICF FORMS
NUS-IWEBS-12	Insert Web 12in (300) - small box 100	ICF WEBS
NUS-IWEBS-06	Insert Web 6in (150) - small box 100	ICF WEBS
NUS-A4XWC-00	4-Way Web Connector (box 100)	ACCESSORIES
NUS-I0096-08	8in Standard Straight	ICF FORMS
NUS-I0090-08	8in Standard 90 Corner	ICF FORMS
NUS-IWEBS-08	Insert Web 8in (200) - small box 100	ICF WEBS
NUS-A0ECF-08	End Caps 203mm (8in)	ACCESSORIES
NUS-ABLOK-08	Form-Lock 203mm (8in) - 3.048 m pieces	ACCESSORIES
NUS-VJC-BOX	VJC Clips (50 clips per box)	ACCESSORIES
NUS-FT-BOX	Fibre Tape (rolls; 10 per box)	ACCESSORIES
NUS-PT-BOX	Protective Tape (rolls; 4 per box)	ACCESSORIES
NUS-SF-BOX	Spray Foam (cans; 12 per box)	ACCESSORIES

DETAILED BILL OF MATERIALS

SKU	Description	Category
NUS-IXPAN-00	450 core - XR35 Panel (unassembled)	ICF FORMS
NUS-I0B96-00	450 core - Unassembled Brick Ledge 96in (bundle 2 BL + 2 std panels)	ICF FORMS
NUS-IWEBS-12	Insert Web 12in (300) - small box 100	ICF WEBS
NUS-IWEBS-06	Insert Web 6in (150) - small box 100	ICF WEBS
NUS-A4XWC-00	4-Way Web Connector (box 100)	ACCESSORIES
NUS-I0096-08	8in Standard Straight	ICF FORMS
NUS-I0090-08	8in Standard 90 Corner	ICF FORMS
NUS-I0B96-00	200 core - Unassembled Brick Ledge 96in (bundle 2 BL + 2 std panels)	ICF FORMS
NUS-IWEBS-08	Insert Web 8in (200) - small box 100	ICF WEBS
NUS-A0ECF-08	End Caps 203mm (8in)	ACCESSORIES
NUS-ABLOK-08	Form-Lock 203mm (8in) - 3.048 m pieces	ACCESSORIES
NUS-VJC-BOX	VJC Clips (50 clips per box)	ACCESSORIES
NUS-FT-BOX	Fibre Tape (rolls; 10 per box)	ACCESSORIES
NUS-PT-BOX	Protective Tape (rolls; 4 per box)	ACCESSORIES
NUS-SF-BOX	Spray Foam (cans; 12 per box)	ACCESSORIES

Pack Size	Priced By	Your Rate (
2	Per Each	
4	Per Each	
100	Per Each	
100	Per Each	
100	Per Each	
3	Per Each	
6	Per Each	
100	Per Each	
30	Per Bundle	
10	Per Bundle	
50	Per Bundle	
10	Per Bundle	
4	Per Bundle	
12	Per Bundle	

Qty Req.	Pack Size	Packs	Supplied	Priced By	Rate (£)
40	2	20	40	Per Each	
8	4	2	8	Per Each	
302	100	4	400	Per Each	
302	100	4	400	Per Each	
302	100	4	400	Per Each	
69	3	23	69	Per Each	
7	6	2	12	Per Each	
8	4	2	8	Per Each	
48	100	1	100	Per Each	
7	30	1	30	Per Bundle	
17	10	2	20	Per Bundle	
208	50	5	250	Per Bundle	
3	10	1	10	Per Bundle	
6	4	2	8	Per Bundle	
5	12	1	12	Per Bundle	

Basis / Note	Extended Total (£
W1 7.7 m x 7 courses, both faces; 40.0 panels net +5%	0.00
W1 top course: corbel (brick ledge) inside, straight outside	0.00
450 core = 12in + 6in web per position; 287 positions @ 203 c/c +5%	0.00
paired with 12in web	0.00
one per web pair	0.00
W2 + W3 200 core, 24.77 m run x 7 courses; 65.5 net +5%	0.00
W2/W3 corner, 7 courses (per sketch)	0.00
W3 top course corbel inside / straight outside (2.9 forms +5%)	0.00
24 webs per brick-ledge bundle (catalogue p15)	0.00
W3 end at the existing basement	0.00
first + last course, 200 core (none made for 450)	0.00
2 per vertical joint	0.00
1 roll / 50 forms	0.00
per course perimeter, both sides	0.00
1 can / 22 forms	0.00

PRICING SUMMARY (from your rates)

ICF FORMS	£0.00
ICF WEBS	£0.00
ACCESSORIES	£0.00
TOTAL (ex VAT)	£0.00

BASIS OF TAKE-OFF

- Source: M. Whalley sketch 'Basement Extension' (29.10.26) - 7.7 m x 18 m outside, three walls, open side against the existin
- Height: 7 courses (3,200 mm) - per sketch '7 corner blocks needed'; confirm against the official drawing when issued.
- W1 (7.7 m) = 450 core: Nudura unassembled panels + 12in and 6in insert webs joined by 4-Way Web Connectors (~457 mm
- W1/W2 junction: 450-to-200 transition formed from straight panels (no corner forms, per sketch).
- W2 (18 m) and W3 (7.7 m) = 8in (200) Standard; 7 x 8in 90 corners at the W2/W3 corner.
- Top course of both short walls: internal corbel (brick ledge) / external straight, per sketch.
- Stock supply, uncut, +5% waste on forms, panels and webs. Accessories per BuildEase standard ratios.
- Alignment/bracing, rebar, concrete and the connection to the existing basement are by others / Ethos.

QUERIES / RFIs

- Official extension drawing to confirm 7.7 x 18 m, 7 courses (3,200 mm) and how the new walls tie into the existing basemen
- 450 core build-up: 12in + 6in insert webs on a 4-Way Web Connector NUS-A4XWC-00 (~457 mm core) - adopted by Tremco
- 450 core panels = NUS-IXPAN-00 XR35 Panel; insert webs NUS-IWEBS-12 / -06 + 4-Way Web Connector NUS-A4XWC-00 (not
panel NUS-I0B96-00 to be confirmed.
- 450 core openings (if any are added): timber bucks + heads by others first, or unassembled panels cut to suit - Nudura end c
- Corbel course: brick-ledge panels supplied for the top course inside face of both short walls - confirm the ledge does not ret